


Location Plan



Local Development Plan Provisions

1.0 GENERAL PROVISIONS

1.1 The requirements of the City of Wanneroo District Planning Scheme No. 2, the Residential Design Codes (R-Codes) and Local Planning Policy 4.19: Medium-Density Housing Standards (RMD-Codes) apply.

2.0 RESIDENTIAL DESIGN CODE AND ZONE

LOTS APPLICABLE	R-CODE DENSITY AND ZONING
Lots 2066-2067, 2080-2083, 2089-2092, 2110-2120, 2153-2160	RMD40

3.0 ACOUSTIC REQUIREMENTS

LOTS APPLICABLE	REQUIREMENTS
Lots 2111-2117, 2119, 2153-2160	3.1 Façade protection treatments (Quiet House Design Measures) as defined in the Lloyd George Noise Assessment dated 4 July 2019 are required for the following: Upper Floor; Lots 2111-2117, 2119, 2153-2160 as per Package 'A' Details of the Quiet House Design Requirements are included in Attachment 1.

4.0 DEVELOPMENT STANDARDS

4.1 For Lots 2067, 2111, 2117, 2119 & 2153, garage locations are to be provided as shown on the LDP.

Legend

Extent of Local Development Plan	Retaining Walls (by developer)
Primary Dwelling Orientation	Lots Subject to Quiet House Design Requirements
Secondary Dwelling Orientation	Designated Garage Locations

Local Development Plan - Atelier North Stage 3A

TRINITY ESTATE ALKIMOS

A Northern Corridor Developments Ltd Project



Endorsement Table

This Local Development Plan has been approved by Council under Clause 52(1)(a) of the Deemed Provisions of District Planning Scheme No. 2

Manager, Approval Services
City of Wanneroo

23/08/2021

Date:

plan:
20/012/043B

scale:
1:1200@A3 | 1:600@A1

date:
23/07/2021

grid:
PCG 94

aerial:
-

designed:
KS

checked:
KS

drawn:
BR

Taylor Burrell Barnett Town Planning & Design
Level 7, 160 St Georges Terrace, Perth WA 6000
e: admin@tbbj.townplanning.com.au
p: (08) 9226 4276

© COPYRIGHT TAYLOR BURRELL BARNETT. ALL RIGHTS RESERVED.
ALL AREAS AND DIMENSIONS DISPLAYED ARE SUBJECT TO DETAIL SURVEY.

ATTACHMENT 1 - QUIET HOUSE DESIGN PACKAGES - LLOYD GEORGE ACOUSTICS

Package A

Area	Orientation to Road or Rail Corridor	Package A (up to 60 dB $L_{Aeq(Day)}$ and 55 dB $L_{Aeq(Night)}$)
Bedrooms	Facing	<input type="checkbox"/> Windows systems: Glazing up to 40% of floor area (minimum $R_w + C_{tr}$ 28) – 6mm thick glass (monolithic, toughened or laminated) in fixed sash, awning or casement opening with seals to openings.
	Side	<input type="checkbox"/> Windows systems: As above.
	Opposite	No requirements
Other Habitable Rooms Including Kitchens	Facing	<input type="checkbox"/> Windows and external door systems: Glazing up to 60% of floor area (minimum $R_w + C_{tr}$ 28) – 6mm thick glass (monolithic, toughened or laminated) in fixed sash, awning or casement opening with seals to openings. Doors to be either 35mm thick solid timber core door with full perimeter acoustic seals. Glazed inserts to match the above. Sliding glass doors to be same performance including brush seals.
	Side	<input type="checkbox"/> Windows and external door systems: As above.
	Opposite	No requirements
General	Any	<input type="checkbox"/> Walls (minimum $R_w + C_{tr}$ 45) – Two leaves of 90mm thick brick with minimum 50mm cavity <input type="checkbox"/> Roof and ceiling (minimum $R_w + C_{tr}$ 35) – Standard roof construction with 10mm plasterboard ceiling and minimum R2.5 insulation between ceiling joists. <input type="checkbox"/> Eaves to be closed using 4mm compressed fibre cement sheet. <input type="checkbox"/> Mechanical ventilation – Refer following pages.
Outdoor Living Area		<input type="checkbox"/> Boundary wall to be minimum 2m high; or <input type="checkbox"/> Locate on the side of the building that is opposite to the corridor; or <input type="checkbox"/> Locate within alcove area so that the house shields it from corridor.

Note: Any penetrations in a part of the building envelope must be acoustically treated so as to not downgrade the performance of the building elements affected. Most penetrations in external walls such as pipes, cables or ducts can be sealed through caulking gaps with non-hardening mastic or suitable mortar.

Mechanical Ventilation requirements

It is noted that natural ventilation must be provided in accordance with F4.6 and F4.7 of Volume One and 3.8.5.2 of Volume Two of the National Construction Code. Where the noise *limit* is likely to be exceeded, a mechanical ventilation system is usually required. Mechanical ventilation systems will need to comply with AS 1668.2 – *The use of mechanical ventilation and air-conditioning in buildings*.

In implementing the acceptable treatment packages, the following must be observed:

- Evaporative air conditioning systems will meet the requirements for Packages A and B provided attenuated air vents are provided in the ceiling space and designed so that windows do not need to be opened.
- Refrigerant based air conditioning systems need to be designed to achieve fresh air ventilation requirements.
- External openings (e.g. air inlets, vents) need to be positioned facing away from the transport corridor where practicable.
- Ductwork needs to be provided with adequate silencing to prevent noise intrusion.